



Project Requirements:	estimate
Granite Curbing: (R&R; 110lf, New; 30lf)	\$7,140
Walkway and Ramp Work:	\$12,550
Rain Garden: 200sf	\$20,000
Utility Adjustments	\$800
Pavement Markings:	\$1,200
Signs:	\$2,750
Total w/ Contingency	\$47,000

# Herbert & Magnolia Field; Curb Extension

**SIGN LIST:**

**PEDESTRIAN CROSSING SIGNS:**

- W11-2 (4) (30" x 30") High Visibility Yellow
- W16-7PL (2)
- W16-7PR (2)
- placed on each side of street
- placed on each side of sign post (duplicative)

**ADVANCED WARNING SIGNS:**

- W11-2 (30" x 30") High Visibility Yellow
- Placard "Ahead" W16-9 Hi-vis

**OBJECT MARKER**

- OM3-L
- placed within rain garden area facing on-coming traffic

**Traffic Calming Items Includes:**

- Curb Extensions
- Curb Ramps/Sidewalks
- Pedestrian Crossing Signs
- Advanced Warning Signs
- Street Light Analysis





